BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/09/2020-21 Dated: 29-01-2021

APPROVED TENDER SCHEDULE –'B'

Item 16

Name of Work :-Anganawadi buildings and Improvements of Government school buildings in ward no:04 of Yelahanka satellite town sub division

Sl	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri T S Kothanda Raju (Proprietor R K CONSTRUCTIONS, Proprietor SHREE CHARAN CONSTRUCTIONS)	
				Rate	Rate in Words
1	Earthwork in surface excavation for levelling and lowering the ground manually (Other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift up to 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled including breaking of clods and neatly dressed as per specifications.	Cum	234.87	281.96	Two Hundred EightyOne Paise NinetySix Only
2	Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20 ems. in depth, compacting each deposited layer by ramming after watering with lead upto 50 m. and lift upto 1.5 m. including cost of all labour complete as per specifications.	Cum	153.58	227.61	Two Hundred TwentySeven Paise SixtyOne Only
3	Providing and injecting chemical emulsion for Pre-constructional Anti-Termite Treatment, creating continuous chemical barrier under and around the column pits, walls, trenches, basement excavation, top surface of the plinth filling, junction of wall and floor, along the external perimeter of building, expansion joints, over the top surface of consolidated earth on which apron is to be laid, surrounding of pipes and conduits, with chloropyriphos emulsifiable concentrates of 20% concentration at 3.19 Litre/sqm., including cost of chemical, diluting in water to one percent concentration, labour, HOM complete as per specifications. (Plinth area of the building at ground floor only shall be measured.)	Sqm	214.54	120.03	One Hundred Twenty Paise Three Only
4	Providing and laying in position plain cement concrete of Mix 1:2:4 with OPC @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregtes @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 ems. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications.	Cum	14.95	6139.76	Six Thousand One Hundred ThirtyNine Paise SeventySix Only

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾ...
ಯಲಹಂಕ ವಿಭಾಗ

5	Providing and laying in position plain cement concrete of Mix 1:2:4 with OPC @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregtes @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 ems. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications.	Cum	12.50	6207.71	Six Thousand Two Hundred Seven Paise SeventyOne Only
6	KSRB 4-1.7 : Providing and laying in position plain cement concrete of Mix 1 :3:6 with OPC @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.69 cum and fine aggregtes @ 0.56cum, machine mixed, concrete laid in layers not exceeding 15 ems. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications.Specification No. KBS 4.1, 4.2	Cum	26.99	6011.81	Six Thousand Eleven Paise EightyOne Only
7	Providing 20mm thick cement plaster (cement mortar 1:4) in single coat with cement mortar, to stone masonry & concrete surface including rounding off comers wherever required smooth rendering, including providing and removing scaffolding, cost of materials, labour, curing etc., complete as per specification.	Sqm	102.76	306.87	Three Hundred Six Paise EightySeven Only
8	Providing floating coat of cement to plastering and finishing smooth, including cost of materials, labour, curing completeas per specifications	Sqm	102.76	21.52	TwentyOne Paise FiftyTwo Only
9	Providing and laying in position reinforced cement concrete of design Mix M25 with OPC @ 340kgs, with 20mm anddown size graded granite metal coarse aggregates @0.70cum and fine aggregtes @ 0.47cum, with super plasticisers @31ts confirming to 189103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 ems thick, vibrated for all works in ground floor level for roof slabs, staircase, lintels and beams retaining walls, return walls, walls (any thickness) including attached pilasters, columns, lintles, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM curing, complete but excluding cost of reinforcement as per specifications	Cum	42.08	6845.24	Six Thousand Eight Hundred FourtyFive Paise TwentyFour Only
10	Providing and laying in position reinforced cement concrete of design Mix M25 with OPC @ 340kgs, with 20mm anddown size graded granite metal coarse aggregates @0.70cum and fine aggregtes @ 0.47cum, with super plasticisers @31ts confirming to 189103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 ems thick, vibrated for all works in ground floor level for roof slabs, staircase, lintels and beams retaining walls, return walls, walls (any thickness) including attached pilasters, columns, lintles, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM curing, complete but excluding cost of reinforcement as per specifications.	Cum	78.45	6845.24	Six Thousand Eight Hundred FourtyFive Paise TwentyFour Only

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬೃಹತ್ ಬೆಂಗಳೂರು ವಿಶ್ವೇಶ್ವರನಗರ ಪಾಲಿಕೆ
ಯಲಹಂಕ ವಿಭಾಗ

	Providing and laying in position reinforced cement concrete of design Mix M25 with OPC @ 340kgs, with 20mm anddown size graded granite metal coarse aggregates @0.70cum and fine aggregtes @ 0.47cum, with super plasticisers @31ts confirming to 189103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 ems thick, vibrated for all works in ground floor level for roof slabs, staircase, lintels and beams retaining walls, return walls, walls (any thickness) including attached pilasters, columns, lintles, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM curing, complete but excluding cost of reinforcement as per specifications.	Cum	63.35	6913.18	Six Thousand Nine Hundred Thirteen Paise Eighteen Only
12	Providing and laying in position reinforced cement concrete of design Mix M25 with OPC @ 340kgs, with 20mm anddown size graded granite metal coarse aggregates @0.70cum and fine aggregtes @ 0.47cum, with super plasticisers @31ts confirming to 189103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 ems thick, vibrated for all works in ground floor level for roof slabs, staircase, lintels and beams retaining walls, return walls, walls (any thickness) including attached pilasters, columns, lintles, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM curing, complete but excluding cost of reinforcement as per specifications.	Cum	17.15	6913.18	Six Thousand Nine Hundred Thirteen Paise Eighteen Only
13	Providing and laying in position reinforced cement concrete of design Mix M25 with OPC @ 340kgs, with 20mm anddown size graded granite metal coarse aggregates @0.70cum and fine aggregtes @ 0.47cum, with super plasticisers @31ts confirming to 189103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 ems thick, vibrated for all works in ground floor level for roof slabs, staircase, lintels and beams retaining walls, return walls, walls (any thickness) including attached pilasters, columns, lintles, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM curing, complete but excluding cost of reinforcement as per specifications.	Cum	5.58	6845.24	Six Thousand Eight Hundred FourtyFive Paise TwentyFour Only
14	Providing and laying in position reinforced cement concrete of design Mix M20 with OPC @ 27.20kgs, with 12mm and down size graded granite metal coarse aggregates @0.05865cum and fine aggregtes @ 0.0391 cum, with super plasticisers @0.2251ts, machine mixed, well compacted for plain chajja of 8.5 ems. average thickness, upto ground floor level, including cost of all materials, labour, HOM finishing, curing, complete but excluding cost of reinforcement as per specifications.	Cum	17.04	561.66	Five Hundred SixtyOne Paise SixtySix Only

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ
ಯಲಹಂಕ ವಿಭಾಗ

15	Providing and laying in position reinforced cement concrete of design Mix M20 with OPC @ 27.20kgs, with 12mm and down size graded granite metal coarse aggregates @0.05865cum and fine aggregtes @ 0.0391 cum, with super plasticisers @0.2251ts, machine mixed, well compacted for plain chajja of 8.5 ems. average thickness, upto ground floor level, including cost of all materials, labour, HOM finishing, curing, complete but excluding cost of reinforcement as per specifications.	Cum	23.10	567.32	Five Hundred SixtySeven Paise ThirtyTwo Only
16	Providing and removing centering, shuttering, strutting,propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials,labour complete as per specifications.	Sqm	184.86	292.15	Two Hundred NinetyTwo Paise Fifteen Only
17	Providing and removing centering, shuttering, strutting,propping etc., and removal of form work for columns, pillars, postand struts, square I rectangular/ polygon in plan including cost of allmaterials, labour complete as per specifications.	Sqm	247.71	516.37	Five Hundred Sixteen Paise ThirtySeven Only
18	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1m in depth including cost of all materials, labour completeas per specifications.	Sqm	519.58	330.65	Three Hundred Thirty Paise SixtyFive Only
19	Providing and removing centering, shuttering. Strutting, proping etc. and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200mm including cost of all materials, labour complete as per specifications.	Sqm	623.66	498.25	Four Hundred NinetyEight Paise TwentyFive Only
20	Providing and removing centering, shuttering, strutting, propping etc., and removal offormworkforsides and soffits of beams, beams haunchings, cantilever, girders, bressumers and lintels exceeding 1m in depth including cost of all materials, labour complete as per specifications.	Sqm	45.16	456.35	Four Hundred FiftySix Paise ThirtyFive Only
21	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for chajja, corbels etc., including edges including cost of all materials, labour complete as per specifications.	Sqm	53.06	365.76	Three Hundred SixtyFive Paise SeventySix Only
22	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for Stairs (excluding landing) except spiral staircase including cost of all materials, labour complete as per specificaiton.	Sqm	44.17	588.84	Five Hundred EightyEight Paise EightyFour Only
23	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and I or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specifications. and Lift charges for steel of all diameters for additional floors over ground floor per floor height of 3.5 m. or part there of cost of labour, complete as per specifications.	MT	12.89	80360.48	Eighty Thousand Three Hundred Sixty Paise FourtyEight Only

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರವರ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಕಾರ್ಯಪಾಲಕ ಪಾಲಿಕೆ
ಯಲಹಂಕ ವಿಭಾಗ

	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and I or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specifications. and Lift charges for steel of all diameters for additional floors over ground floor per floor height of 3.5 m. or part there of cost of labour, complete as per specifications. - .do-TMT bars Fe 500	MT	2.56	81207.50	EightyOne Thousand Two Hundred Seven Paise Fifty Only
25	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and I or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specifications. and Lift charges for steel of all diameters for additional floors over ground floor per floor height of 3.5 m. or part there of cost of labour, complete as per specifications. - .do-TMT bars Fe 500	MT	7.64	81207.50	EightyOne Thousand Two Hundred Seven Paise Fifty Only
26	Providing and fixing stainless steel 304 grade for staircase railings,balconies, ramps, with hand rail, 50mm dia 16 guage hollow pipe welded to vertical hollow 50mm dia pipe of 16 guage, stainless steelvertical pipe spaced at 1.20m regular intervals and 5 Nos of 25mm dia. Stainless steel hollow horizontal pipe are welded to vertical 50mm dia hollow pipe. The entire assembly is fixed to staircase concrete by using expansion bolts by drilling concrete etc., complete including cost of materials, labour, HOM of and electrical charges, etc., complete as per specifications.	Sqm	21.10	6818.06	Six Thousand Eight Hundred Eighteen Paise Six Only
27	Providing and constructing granite I trap I basalt size stone masonry in foundation with cement mortar, stone hammered dressed in courses not less than 20 cms high, bond stones at 2m. apart in each course including cost of materials, labour, curing complete as per specifications.	Cum	25.90	5204.42	Five Thousand Two Hundred Four Paise FourtyTwo Only
28	KSRB 6-2 : Providing and constructing burnt brick masonry with approved quality of non-modular bricks of standard size of class designation 5.0 Newton per sqmm (table moulded) with cement mortar 1:6 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications.Specification No. KBS 6.2	Cum	111.37	7597.14	Seven Thousand Five Hundred NinetySeven Paise Fourteen Only
29	KSRB 6-2 : Providing and constructing burnt brick masonry with approved quality of non-modular bricks of standard size of class designation 5.0 Newton per sqmm (table moulded) with cement mortar 1:6 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications.Specification No. KBS 6.2	Cum	47.80	7665.08	Seven Thousand Six Hundred SixtyFive Paise Eight Only

ಕಾರ್ಯನಿರ್ವಾಹಕ ಅಭಿಯಂತ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪ
ಯಲಹಂಕ ವಿಭಾಗ

30	KSRB 15-3.14/15-7: Providing 12mm thick plain plastering in single coat to internal ceiling & RC surfaces in cement mortar 1:4 (1 cement : 4 fine sand) including providing & removing necessary scaffolding, rounding of corners wherever required, smooth rendering with lime, curing etc. including cost of all materials, formwork, labour charges, HOM of Machineries, loading, unloading ,with all lead and lifts etc., compelte & as per specification and as directed by Engineer.	Sqm	244.87	254.79	Two Hundred FiftyFour Paise SeventyNine Only
31	KSRB 15-3.14/15-7: Providing 12mm thick plain plastering in single coat to internal ceiling & RC surfaces in cement mortar 1:4 (1 cement : 4 fine sand) including providing & removing necessary scaffolding, rounding of corners wherever required, smooth rendering with lime, curing etc. including cost of all materials, formwork, labour charges, HOM of Machineries, loading, unloading ,with all lead and lifts etc., compelte & as per specification and as directed by Engineer.	Sqm	532.52	268.37	Two Hundred SixtyEight Paise ThirtySeven Only
32	KSRB15-7 : Providing lime rendering for plastering to wall and ceiling, including cost of materials, labour, curing complete as per specifications.	Sqm	1678.29	36.24	ThirtySix Paise TwentyFour Only
33	KSRB 15-3.5/15-7: Providing 15mm thick plain plastering in single coat to internal masonry surfaces, in cement mortar 1:4 (1 cement : 4 fine sand) including providing & removing necessary scaffolding, rounding of corners wherever required, smooth rendering with lime, curing etc.including cost of all materials, formwork, labour charges, HOM of Machineries, loading, unloading ,with all lead and lifts etc., compelte & as per specification and as directed by Engineer.	Sqm	318.43	250.26	Two Hundred Fifty Paise TwentySix Only
34	KSRB 15-3.5/15-7: Providing 15mm thick plain plastering in single coat to internal masonry surfaces, in cement mortar 1:4 (1 cement : 4 fine sand) including providing & removing necessary scaffolding, rounding of corners wherever required, smooth rendering with lime, curing etc.including cost of all materials, formwork, labour charges, HOM of Machineries, loading, unloading ,with all lead and lifts etc., compelte & as per specification and as directed by Engineer.	Sqm	582.48	263.84	Two Hundred SixtyThree Paise EightyFour Only
35	KSRB15-3 : Providing 18mm thick cement plaster in single coat with cement mortar 1:3 to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specification	Sqm	456.97	312.54	Three Hundred Twelve Paise FiftyFour Only
36	KSRB15-3 : Providing 18mm thick cement plaster in single coat with cement mortar 1:3 to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specification	Sqm	167.16	326.13	Three Hundred TwentySix Paise Thirteen Only

ಕಾರ್ಯಪಾಲಕ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಪಾಲಿಕೆ
ಯಲಹಂಕ ವಿಭಾಗ

	KSRB 15-3.5/15-4.7: Providing 15mm thick plain plastering in single coat to external masonry surfaces, in cement mortar 1:4 (1 cement : 4 fine sand) including providing & mixing water proofing compound of approved quality and make as admixture to cement mortar as per manufacturer's specifications, providing & removing necessary scaffolding, rounding of corners wherever required, sponge finishing, curing etc. including cost of all materials, formwork, labour charges, HOM of Machineries, loading, unloading ,with all lead and lifts etc., compelte & as per specification and as directed by Engineer.	Sqm	159.19	313.67	Three Hundred Thirteen Paise SixtySeven Only
38	Providing applying two coats of wall putty to inside plastered walls and ceiling using white cement putty. Scrapping and levelling the surface using steel blade and preparing the surface even and smooth by using different grade sand papers, including cost of all materials, cost of labour and scaffolding etc., complete as per the specification.KSRB 15-15.1 : Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications.. with primer Internal Masonry wall surfaces	Sqm	563.30	133.62	One Hundred ThirtyThree Paise SixtyTwo Only
39	Providing applying two coats of wall putty to inside plastered walls and ceiling using white cement putty. Scrapping and levelling the surface using steel blade and preparing the surface even and smooth by using different grade sand papers, including cost of all materials, cost of labour and scaffolding etc., complete as per the specification.KSRB 15-15.1 : Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications.. with primer Internal Masonry wall surfaces	Sqm	1115.00	138.15	One Hundred ThirtyEight Paise Fifteen Only
40	Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications.	Sqm	616.16	124.56	One Hundred TwentyFour Paise FiftySix Only
41	Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications.	Sqm	167.16	129.09	One Hundred TwentyNine Paise Nine Only

ಕಾರ್ಯನಿರ್ವಾಹಕ ಅಭಿಯಂತರರು
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

42	KSRB 15-17.4 : Applying priming coat over new wood surface and I or wood based surface, after brushing with ready mix enamel priming paint including preparing the surface after thoroughly cleaning oil, grease, dirt and foreign matter, sand papering and knotting ready mix paint including cost of materials, labour, complete as per specifications.	Sqm	32.96	56.62	FiftySix Paise SixtyTwo Only
43	KSRB 15-17.4 : Applying priming coat over new wood surface and I or wood based surface, after brushing with ready mix enamel priming paint including preparing the surface after thoroughly cleaning oil, grease, dirt and foreign matter, sand papering and knotting ready mix paint including cost of materials, labour, complete as per specifications.	Sqm	10.08	61.15	SixtyOne Paise Fifteen Only
44	KSRB 15-17.6 : Providing and applying painting two coats (excluding priming coat) on new wood surface and I or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, complete as per specifications.	Sqm	32.96	109.84	One Hundred Nine Paise EightyFour Only
45	KSRB 15-17.6 : Providing and applying painting two coats (excluding priming coat) on new wood surface and I or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, complete as per specifications.	Sqm	10.08	114.37	One Hundred Fourteen Paise ThirtySeven Only
46	Applying red lead ready mix priming coat over new steel or other metal surface including preparing the surface after throughly cleaning oil, grease, dirt and other foreign matter, and scoured with wire brushes, fine steel wool, sand papers including cost of materials, labour, complete as per specifications. KSRB 15-18.2 : Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications.	Sqm	38.46	154.00	One Hundred FiftyFour Only
47	Applying red lead ready mix priming coat over new steel or other metal surface including preparing the surface after throughly cleaning oil, grease, dirt and other foreign matter, and scoured with wire brushes, fine steel wool, sand papers including cost of materials, labour, complete as per specifications. KSRB 15-18.2 : Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications.	Sqm	37.17	163.06	One Hundred SixtyThree Paise Six Only

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ
ಯಲಹಂಕ ವಿಭಾಗ

	Providing and fixing Vitrified glazed tiles of approved make, quality . & colour of size 600 x 600 x 1 Omm thick fixed on bed of 12mm thickcement mortar for flooring, skirting and jointed with neat cement slurrymixed with pigment to mach shade of tiles, including providing spacersat required interval and removing stains, including cost of all mateirals,mortar, labour, etc., Complete as per specification.	Sqm	182.02	1105.20	One Thousand One Hundred Five Paise Twenty Only
49	Providing and fixing Vitrified glazed tiles of approved make, quality & colour of size 600 x 600 x 1 Omm thick fixed on bed of 12mm thickcement mortar for flooring, skirting and jointed with neat cement slurrymixed with pigment to mach shade of tiles, including providing spacersat required interval and removing stains, including cost of all mateirals,mortar, labour, etc., Complete as per specification.	Sqm	127.06	1107.47	One Thousand One Hundred Seven Paise FourtySeven Only
50	Providing and fixing Special make glazed Vitrified tiles (Granomite finish) of approved make, quality and colour of size 600x600x10mm thick fixed on existing flooring with a special adhesive for flooring, skirting and jointed with neat cement slurry mixed with pigment to match shade of tiles, including providing spacers at required interval and removing stains etc., cost of materials, mortar, labour etc., complete as per specification.	Sqm	152.67	1246.75	One Thousand Two Hundred FourtySix Paise SeventyFive Only
51	KSRB15-5 :Providing rough cement-plastering15mm thick in single coat with cement mortar to brick masonry for base of dadooing works with sand of approved quality, providing and removing scaffolding,including cost of materials, labour, curing complete as per specifications.	Sqm	3.41	217.42	Two Hundred Seventeen Paise FourtyTwo Only
52	KSRB15-5 :Providing rough cement-plastering15mm thick in single coat with cement mortar to brick masonry for base of dadooing works with sand of approved quality, providing and removing scaffolding,including cost of materials, labour, curing complete as per specifications.	Sqm	13.41	224.21	Two Hundred TwentyFour Paise TwentyOne Only
53	"Providing and fixing skirting of 100mm high with Vitrified tiles of 10mm minimum thick of first quality and of approved make & sample, conforming to IS specifications, laid on a bed of 12mm thick cement mortar 1:3 (1 cement : 3 fine sand) with a thin coat of cement slurry on a prepared bed / floor slabs including finishing the joints with matching coloured cement, oxalic acid wash, waxing, curing etc. with all lead and lift etc. complete as per the directions of the Engineer-in-charge including cost & conveyance of all materials, cost of labour for all items of work, equipment and all other incidental charges for the successful completion of the work	Sqm	118.36	110.74	One Hundred Ten Paise SeventyFour Only
54	Providing skirting, dadoing, rises of steps with colour glazed tiles on 10mm thick cement plaster 1:3 and jointed with white cement slurry over existing rough plaster surface using glazed tiles of approved make and size including cost of materials, labour, completeas per specifications.	Sqm	27.12	1439.25	One Thousand Four Hundred ThirtyNine Paise TwehtyFive Only

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

55	Providing skirting, dadoing, rises of steps with colour glazed tiles on 10mm thick cement plaster 1:3 and jointed with white cement slurry over existing rough plaster surface using glazed tiles of approved make and size including cost of materials, labour, completeas per specifications.	Sqm	20.37	1441.52	One Thous… Four Hundr… FourtyOne Pais… FiftyTwo Only
56	Providing and laying flooring using prepolished, water cut/gang saw 19mm thick granite laid over bed of 20mm thick 1:4 cm & jointed with neat cement slurry mixed with pigment to mach shade of granite slabs including laying POP on finished surface and cleaning the surface, including the cost of all materials and labours etc., complete as per specifications.-do- using silver grey granite/Multy Red/Ruby Red/Black/ Hassan Green Granite of width not less than 1200mm.	Sqm	11.07	3101.59	Three Thousand One Hundred One Paise FiftyNine Only
57	KSRB 14.14-5: Providing Ceramic tiles of approved make,shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment , including cost of materials, labour, curing, complete as per specifications. - for Ceramic Tiles of size 15x15cms 6mm thick	Sqm	1.80	1275.06	One Thousand Two Hundred SeventyFive Paise Six Only
58	Providing wood frames of doors, windows, clerestorywindows, ventilators and other frames, wrought, framed or assembledincluding making plaster groves (excluding cost of cement concrete andside clamps), but including cost of materials, labour, HOM complete as per specifications.White Sal wood frames	Sqm	1.04	68563.34	SixtyEight Thousand Five Hundred SixtyThree Paise ThirtyFour Only
59	Fixing of Door frames in an existing opening including embedding frame in floor and walls after cutting masonry for embedding holdfasts including providing & fixing 3/4 of MS hold fasts of size 200x20x3mm for each side and fixed to the frame and embeded with PCC 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20mm nominal size), painting two coats of coal tar to sides of frames, making good the damages to walls & floor as required and disposal of debris including cost of materials, labour, HOM of machineries complete as per specifications all as per the drawing and as per the directions of the Engineer-in-charge of the work	Nos	8.00	1546.83	One Thousand Five Hundred FourtySix Paise EightyThree Only
60	Fixing of Door frames in an existing opening including embedding frame in floor and walls after cutting masonry for embedding holdfasts including providing & fixing 3/4 of MS hold fasts of size 200x20x3mm for each side and fixed to the frame and embeded with PCC 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20mm nominal size), painting two coats of coal tar to sides of frames, making good the damages to walls & floor as required and disposal of debris including cost of materials, labour, HOM of machineries complete as per specifications all as per the drawing and as per the directions of the Engineer-in-charge of the work	No	5.00	1551.36	One Thousand Five Hundred FiftyOne Paise ThirtySix Only

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾ

	Providing and fixind of factory made 30mm P.V.C rigid foam PANEL DOORS made from MS tube of 19 guage, size of 19mm x 19mm and covered with heat moulded PVC C Channel of 5 mm thick and width of 50mm to form styles and rails. The inner panel should be inserted in between the frame with 5mm thick PVC rigid foam sheet, weldedfsealed to the styles and rails along with 5mm PVC, heeding on all and either sides. The vertical tubes may be filled with suitable wood material to further enhance the screw holding capacity	Sqm	1.89	2722.24	Two Thousand Seven Hundred TwentyTwo Paise TwentyFour Only
62	Providing and fixing in position fully panelled wood shutters for doors, styles and rails of 30mm. thick with bottom and lock rails 180mm wide top rail and styles 1 OOmm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM complete as per specifications. (excluding cost of fixtures) Specification No. KBS 9.34	Sqm	25.16	4920.19	Four Thousand Nine Hundred Twenty Paise Nineteen Only
63	Providing and fixing in position fully panelled wood shutters for doors, styles and rails of 30mm. thick with bottom and lock rails 180mm wide top rail and styles 1 OOmm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM complete as per specifications. (excluding cost of fixtures) Specification No. KBS 9.34	Sqm	15.08	4924.72	Four Thousand Nine Hundred TwentyFour Paise SeventyTwo Only
64	KSRB 7.8 : Providing and fixing in position in cement concrete 1:3:6 steel glazed windows and ventilators side hung/top hung 2/3 openable 1/3 fixed as per approved drawings using Z angles of 25x33x3mm, weighing 1.419 kg/m both for outer and inner frames and central mullion section of size 25x46x3mm, weighing 2.28kg/m all duly providing T section 19x19x3mm weighing 0.839 kg/m for glazing of windows, not more than 34 ems. c to c including providing and fixing 4mm. thick reeded glass with teakwood beading of required size, all steel sections should confirm to I.S 7452:1990, 4nos. of holdfasts of approved size, section should be cut to length welded and grinded electrically subdividing frames of unit shall be tenonned and revetted into the frames electrically. All the steel surface shall be throughly cleaned free of rust and painted with one coat of anti-corrosive paint and finishing two coats of ready mix paint of approved colour and make including cost of materials, fixtures,labour charges and HOM complete as per specifications.	Sqm	28.80	3768.56	Three Thousand Seven Hundred SixtyEight Paise FiftySix Only

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾ...
ಯಲಪಂಕ ವಿಭಾಗ

65	KSRB 7.8 : Providing and fixing in position in cement concrete 1:3:6 steel glazed windows and ventilators side hung/top hung 2/3 openable 1/3 fixed as per approved drawings using Z angles of 25x33x3mm, weighing 1.419 kg/m both for outer and inner frames and central mullion section of size 25x46x3mm, weighing 2.28kg/m all duly providing T section 19x19x3mm weighing 0.839 kg/m for glazing of windows, not more than 34 ems. c to c including providing and fixing 4mm. thick reeded glass with teakwood beading of required size, all steel sections should confirm to I.S 7452:1990, 4nos. of holdfasts of approved size, section should be cut to length welded and grinded electrically subdividing frames of unit shall be tenonned and revetted into the frames electrically. All the steel surface shall be throughly cleaned free of rust and painted with one coat of anti-corrosive paint and finishing two coats of ready mix paint of approved colour and make including cost of materials, fixtures,labour charges and HOM complete as per specifications	Sqm	48.69	3775.35	Three Thousand Seven Hundred SeventyFive Paise ThirtyFive Only
66	Providing and fixing MS grill work for windows and ventilators weighing 21 kgs./ sqm. using MS flats or MS square bars or combination of MS flats and square bars as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat red lead primer & two coats synthetic enamel paint, cost of materials, fixtures, labour and HOM of machinery complete as per technical specification and as directed by the Engineer-in-Charge of work.with all lead & lift, loading & unloading and all other incidental charges etc.	Kgs	604.80	107.58	One Hundred Seven Paise FiftyEight Only
67	Providing and fixing MS grill work for windows and ventilators weighing 21 kgs./ sqm. using MS flats or MS square bars or combination of MS flats and square bars as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat red lead primer & two coats synthetic enamel paint, cost of materials, fixtures, labour and HOM of machinery complete as per technical specification and as directed by the Engineer-in-Charge of work.with all lead & lift, loading & unloading and all other incidental charges etc.	Kgs	1022.49	114.37	One Hundred Fourteen Paise ThirtySeven Only
68	KSRB 7.1 : Providing and fixing in position collapsible steel shutters with single or double leaf with vertical channel 20mmx1 Ommx2mm braced with flat iron diagonals 20mmx5mm size, with top and bottom rails ofT iron sections of 40x40x6 mm with 38mm dia steel pulleys complete with bolt and nuts, locking arrangements, stoppers, handles on both sides with 7.5cms openings at 10 ems. c to c applying a priming coat of red lead paint. cost of materials, labour, HOM complete as per specifications. size of gate 2.4mx1.4m Specification No. KBS 7.7/7.12	Sqm	4.83	5899.70	Five Thousand Eight Hundred NinetyNine Paise Seventy Only

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ
ಯಲಹಂಕ ವಿಭಾಗ

	Providing and fixing M.S. Gate as per Chief Architect Drawing, using 50mm x 50mm 14 guage M.S. hollow pipe frame work bent to ornamental shape as shown in the drawing and 35mm x 6mm and 16 x 16mm Square rods for verticals alternatively spaced at 4cms clc in two halves and 40mmx6mm .S. flats for horizontal member and at the top cast iron spikes are provided at alternate vertical embers as shown in the drawing etc., complete. All the steel surface should be thoroughly cleaned free of rust and painted with anti corrosive paint (shop paint) etc., complete. The work includes cost of all materials,labour charges for all items of work, hire charges for welding, cutting and grinding equipment, and electricity charges, with lead and lift, loading and unloading charges, etc., complete as per specification.	Sqm	7.50	3459.42	Three Thousand Four Hundred FiftyNine Paise FourtyTwo Only
70	Providing and fixing white vitreous china clay, water closet European type (Pedestal type, S-trap) with black solid plasticseat and lid, C.P brass hinges, rubber buffers. 10 litre white glazed Ivitreous china clay low level, flushing cistern (all are approved make) with fittings, C. I I M.S brackets, 40mm diameter flush bend with fittings	No	1.00	5443.35	Five Thousand Four Hundred FourtyThree Paise ThirtyFive Only
71	Providing and fixing white vitreous china clay, flat back wash basin size 630x450mm with a pair of 15mm C.P brass pillar taps with C.I I M.S brackets, 32 mm C.P. brass waste of standard pattern, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications.	No	1.00	4537.45	Four Thousand Five Hundred ThirtySeven Paise FourtyFive Only
72	Providing and fixing 1500x450mm dia rectangular shape mirror with plastic moulded frame of approved make and shade with 6mm thick hard board backing including cost of materials, labour complete as per specifications	No	1.00	1677.05	One Thousand Six Hundred SeventySeven Paise Five Only
73	Providing . & fixing Polyethelene-Aiuminium-Polyethelene (PE-AL-PE) Composite Pressure Pipes conforming to IS 15450 duly "ISI" marked, U.V. stabalized with Carbon black for hot & cold water supply, capable to withstand temperature upto 80C inCluding all special composite fittings (engineering plastic blend and brass inserts wherever required.) e.g. elbows, tees, reducers, couplers & connectors etc., with clamps at 1.00 meter spacing, cutting & making good the walls etc., including testing complete as required. (Internal work) -1620 (20mm OD) Pipe	m	33.70	242.33	Two Hundred FourtyTwo Paise ThirtyThree Only
74	Providing and fixing CI Nahani trap of approved make conforming to ISI specifications and construction of Cistern in M-15 as per directions (Rate is inclusive of cost of materials and fixtures and conveyance of materials to work spot).	No	1.00	322.73	Three Hundred TwentyTwo Paise SeventyThree Only

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂ...
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನ...
ಯಲಹಂಕ ವಿಭಾಗ

75	Earthwork excavation by manual means for foundation of buildings, water supply and sanitary lines and electrical conduits etc, either in pits or in trenches 1.5m and above in width, in soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. including breaking of clods complete as per specifications.-in ordinary soil.	Cum	0.92	338.58	Three Hundred ThirtyEight Paise FiftyEight Only
76	Providing and fixing sand cast iron soil waste and vent pipes with spun yarn soaked in cement slurry and cement mortar 1 :2 including cost of materials, labour, testing complete as per specifications.	m	33.70	754.17	Seven Hundred FiftyFour Paise Seventeen Only
77	Constructing brick masonry Inspection chamber for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, C.I cover withframe (light duty) internal dimensions. total weight of cover with frame to be not less than 38 kg (weight of cover 23kg and weight of frame 15 kg) R.C.C. top slab with cement concrete M 15 with 20mm and downsize granite metal, foundation concrete M 5 with 40mm and downsize granite metal inside plastering 12mm thick with cement mortar 1 :3, finish smooth with a floating coat of cement on walls and bed concrete complete as per standard design including cost of materials, labour charges, curing complete as per specifications. - 450x300mm and 450mm depth (clear inside dimension) for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, C.I cover withframe (light duty) 450x300mm	Cum	1.00	4303.04	Four Thousand Three Hundred Three Paise Four Only
78	Providing and fixing to wall, ceiling and floor, medium density polyethylene pipes 6.00 kgs/sq.cm working pressure of outside diameter with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor including cost of all materials, labour charges, HOM and testing complete as per specifications.-90 mm dia	m	33.70	430.30	Four Hundred Thirty Paise Thirty Only
79	Providing and fixing in position brass bib cock of approved quality nominal bore including cost of all materials, labour and HOM with all leads complete as per specifications. Specification No.KBS 13.2.2/13.3 20mm nominal dia	Nos	1.00	195.90	One Hundred NinetyFive Paise Ninety Only
80	Providing and fixing in position brass stop cock of approved quality nominal bore including cost of all materials, labour and HOM with all leads complete as per specifications. Specification No.KBS 13.2.2 /13.3 20mm nominal dia	No	1.00	159.67	One Hundred FiftyNine Paise SixtySeven Only
81	Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) nominal bore including cost of all materials, labour and HOM with all leads complete as per specifications.	No	1.00	380.48	Three Hundred Eighty Paise FourtyEight Only

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾ
ಯಲಹಂಕ ವಿಭಾಗ

	Providing & applying water proofing to concrete surfaces using high quality polymer-modified bituminous compounds (confirming to ASTM Sqm D 5147) reinforced with non woven polyester fabric, weighing 180gml sqm granular finish 4mm thick by torch on application method confirming to the properties indicated below. It shall be provided after priming the surface using bitumen primer at 0.2 ltr lsqm. Detailed specification & Methodology 1. Membrane thickness 4mm (+ or - 5%) 2. Tensile strength - Longitudinal 790 N15cm Transverse 730 N15cm 3. Elongation of Membrane - Longitudinal 65% Transverse 69% 4. Tear Resistance -Longitudinal 180 NTransverse 190 N 5. Lap joint strength - Longitudinal 750 N15cm Transverse 550 N15cm 6. Puncture Resistance - Static 1.4 Dynamic 1.3 7. Water absorption - < 0.15% 8. Water permeability - Nil 9. Chemical resistance - Chloride, sulphate and Nitrate The area to be water proofed shall be free from loose aggregate, dust free and in dry condition. Primer must be applied to the surface and allowed to dry prior to application of membrane. The membrane shall be applied within 6 hours after application of primer. The	Sqm	464.24	486.92	Four Hundred EightySix Paise NinetyTwo Only
83	KSRB 13-11.1: Over Head Synthetic Tanks - Providing, Placing on Terrace, Polyethylene storage tanks with manhole lid and suitable locking arrangements, making holes of suitable diametre for inlet,outlet and over flwo pipes including cost of all materials, labour, transport charges, HOM of euipments and testing complete as per specifications for 1000 Litres Capcity including cost of all materials, formwork, labour charges, HOM of Machineries, loading, unloading ,with all lead and lifts etc., compelte & as per specification and as directed by Engineer.	Nos	1.00	7731.89	Seven Thousand Seven Hundred ThirtyOne Paise EightyNine Only
84	Provision for Dismantling of Existing RCC Structure and removing the debris as directed by the Engineer-in-Charge of work.with all lead & lift, loading & unloading and all other incidental charges etc.	Cum	26.98	1766.03	One Thousand Seven Hundred SixtySix Paise Three Only
85	Provision for Dismantling of Existing Brick masonry and removing the debris as directed by the Engineer-in-Charge of work.with all lead & lift, loading & unloading and all other incidental charges etc.	Cum	74.97	397.47	Three Hundred NinetySeven Paise FourtySeven
86	Provision for Dismantling of Existing Joinery Work and Stocking. as directed by the Engineer-in-Charge of work.with all lead & lift, loading & unloading and all other incidental charges etc.	Cum	14.26	753.03	Seven Hundred FiftyThree Paise Three Only
87	Supplying heavy gauge PVC conduit pipe .....mm dia .....mm thick confirming to IS 2509 with suitable size bends, metal/PVC junction boxes, adhesive paste etc., and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures, run with 18SWG GI fish wire wherever necessary 19/20mm dia 2mm thick	m	230.00	41.94	FourtyOne Paise NinetyFour Only

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾ...
ಪಲಕಂಕ ವಿಭಾಗ

88	Supplying heavy gauge PVC conduit pipe .....mm dia .....mm thick confirming to IS 2509 with suitable size bends, metal/PVC junction boxes, adhesive paste etc., and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures, run with 18SWG GI fish wire wherever necessary. 25mm dia 2mm thick	m	370.00	55.57	FiftyFive Paise FiftySeven Only
89	Supplying heavy gauge PVC Conduit Pipe ....dia .....mm thick with suitable size bends, metal junction boxes adhesive paste etc., by groove cutting in the wall and fixing by bracing U or J hooks and cement plastering up to the wall surface and run with 18 SWG GI fish wire run throughout the conduit wherever necessary. 25mm dia 2mm thick	m	80.00	56.62	FiftySix Paise SixtyTwo Only
90	Supplying And Fixing Metal Fan Box with Round Hook.	No	20.00	89.12	EightyNine Paise Twelve Only
91	Supplying and wiring adopting loop system in existing PVC Conduit /casing capping casing capping using 2x1.5Sqmm(Phase & Neutral) & 1x1.0 sqmm (Earth wire) FRLSmulti strand PVC insulated copper wire (confirming toIS-694: and latest amendments) without control switchshall be fixed on the existing plastic sheet/ gang box, theother end of the wires shall be terminated with sufficientloose length in a wood/PVC round block. complete for achoutlet. Short point upto 3Mtr from tapping point to out let via switch box	Point	6.00	167.76	One Hundred SixtySeven Paise SeventySix Only
92	Supplying and wiring adopting loop system in existing PVC Conduit /casing capping casing capping using 2x1.5Sqmm(Phase & Neutral) & 1x1.0 sqmm (Earth wire) FRLSmulti strand PVC insulated copper wire (confirming toIS-694: and latest amendments) without control switchshall be fixed on the existing plastic sheet/ gang box, theother end of the wires shall be terminated with sufficientloose length in a wood/PVC round block. complete for eachoutlet. Medium point above 3Mtr upto 6Mtr from tapping point to out let via switch box.	Point	19.00	262.13	Two Hundred SixtyTwo Paise Thirteen Only
93	Supplying and wiring adopting loop system in existing PVC Conduit /casing capping casing capping using 2x1.5Sqmm(Phase & Neutral) & 1x1.0 sqmm (Earth wire) FRLSmulti strand PVC insulated copper wire (confirming toIS-694: and latest amendments) without control switchshall be fixed on the existing plastic sheet/ gang box, theother end of the wires shall be terminated with sufficientloose length in a wood/PVC round block. complete for eachoutlet. Long point above 6Mtr upto 10Mtr from tapping point to out let via switch box	Point	6.00	393.19	Three Hundred NinetyThree Paise Nineteen Only

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿ
ಯಲಹಂಕ ವಿಭಾಗ

	Supplying and wiring adopting loop system in existing PVC Conduit /casing capping casing capping using 2x1.5Sqmm(Phase & Neutral) & 1x1.0 sqmm (Earth wire) FRLSmulti strand PVC insulated copper wire (confirming toIS-694: and latest amendments) without control switchshall be fixed on the existing plastic sheet/ gang box, theother end of the wires shall be terminated with sufficientloose length in a wood/PVC round block. complete for eachoutlet. Two outlet in a row, above 3Mtr upto 6Mtr from tapping point to out let via switches.	Point	32.00	498.04	Four Hundred NinetyEight Paise Four Only
95	Supplying and wiring adopting loop system in existing PVC Conduit /casing capping casing capping using 2x1.5Sqmm(Phase & Neutral) & 1x1.0 sqmm (Earth wire) FRLSmulti strand PVC insulated copper wire (confirming toIS-694: and latest amendments) without control switchshall be fixed on the existing plastic sheet/ gang box, theother end of the wires shall be terminated with sufficientloose length in a wood/PVC round block. complete for eachoutlet. Three outlet in a row, above 6Mts upto 10Mtr from tapping point to out let via switches box	Point	1.00	707.74	Seven Hundred Seven Paise SeventyFour Only
96	Wiring for lighting/power circuit using one of FRLS PVCinsulated 1100V grade, multistrand copper wire with low conductor resistance single core in open or concealed system of wiring with specified IS-694:confirming to latest amendments. 1.5 sqmm	Mtrs	160.00	21.49	TwentyOne Paise FourtyNine Only
97	Wiring for lighting/power circuit using one of FRLS PVCinsulated 1100V grade, multistrand copper wire with low conductor resistance single core in open or concealed system of wiring with specified IS-694:confirming to latest amendments. 2.5 sqmm	Mtrs	260.00	33.55	ThirtyThree Paise FiftyFive Only
98	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/C.C wall .1-3Way	No	3.00	99.61	NinetyNine Paise SixtyOne Only
99	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/C.C wall10-12Way	No	9.00	173.00	One Hundred SeventyThree Only
100	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box. 1 to 3 Module	No	2.00	115.34	One Hundred Fifteen Paise ThirtyFour Only
101	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box. 10-12 Module	No	9.00	241.16	Two Hundred FourtyOne Paise Sixteen Only
102	Supplying and fixing of modular switch & connected accessories on existing modular switch plate as per IS 3854 and IS 1293. 6Amps one way Switch	No	66.00	73.40	SeventyThree Paise Fourty Only
103	Supplying and fixing of modular switch & connected accessories on existing modular switch plate as per IS 3854 and IS 1293. 6Amps 3way socket	No	12.00	110.09	One Hundred Ten Paise Nine Only

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾ

104	Supplying and fixing of modular switch & connected accessories on existing modular switch plate as per IS 3854 and IS 1293. Stepped Fan Regulator	No	20.00	304.07	Three Hundred Four Paise Seven Only
105	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 withShort circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898. 6-32Amps SP	No	8.00	455.05	Four Hundred FiftyFive Paise Five Only
106	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 withShort circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898. 6-32Amps DP	No	3.00	953.09	Nine Hundred FiftyThree Paise Nine Only
107	Supplying and fixing regular MCB distribution boards on wall / wood board / flush mounting using required clamps, bolts, nuts etc., with provision for fixing suitable type capacity MCB's single phase / 3 phase / single door with powder coated painting. Made out of 14 SWG MS enclosure. 6Way SP &N . Double door	No	3.00	1363.05	One Thousand Three Hundred SixtyThree Paise Five Only
108	Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq.mm wire armoured) confirming to IS-3975:1990 (No.of Strip indicated in GTP & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1988 & confirming to GTP of GROUP-A (55/7.4)4 core 10 sqmm	Mtr	70.00	124.56	One Hundred TwentyFour Paise FiftySix Only
109	Supply of round/square recess/surface mounted rolling type LED Down light with .....W GU 10 LED Lamp RibFabricated from Die cast aluminium with white powdercoated prewired to mains connector & has swiveling unit ofaluminium die cast eye ball & LED Lamp position retained bycircular wire spring, with Life of 25000 burning hours & 70%lumen maintenance with CRI > 80. Power Input: 220-240V@ 50/60Hz & Power factor >0.9 along with CE approved. 2years Warranty against any manufacturing defect working under standard electrical condition. LED square or round down light 10-12W	No	64.00	805.25	Eight Hundred Five Paise TwentyFive Only
110	Supplying capacitor type ceiling fan complete with down rod blades, shackle, canopies etc., foroperation on 230 volts, 50 cycles. Single phase AC supply conforming to ISS-374- 1979 and with double ball bearing system.56" Sweep (1400mm) Regular model	No	20.00	2230.16	Two Thousand Two Hundred Thirty Paise Sixteen Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.